intertek
Total Quality. Assured.

中国认可
国际互认
检测
TESTING
CNAS L0220

TEST REPORT

Number: GZHT91025679(S1)

Applicant: TRECK SA
SANTA ROSA 5220 SAN
JOAQUIN SANTIAGO CHILE

Attn: Andres Gandara

Date: Apr 01, 2021
THIS IS TO SUPERSEDE REPORT NO. GZHT91025679 DATED MAR 23, 2021

Sample Description:

One and a half (1.5) pairs of submitted samples said to be Men's lace up safety boots in Black/Blue.

Standard	:	ASTM F2413-18
Size	:	US 9
Buyer's Name	:	--
Ref. No	:	V93
Brand	:	--
Manufacturer	:	--
Colour	:	Black/Blue
Vendor	:	--
Supplier	:	--
P.O. No.	:	--
Ref.	:	Upper: Blue Textile Lining: Blue Sandwich Lining Toe Cap: Composite Toe Cap Insole/Plate: Non-Metallic Anti-Penetration Midsole Insock: Mesh + PU Sole: SK211, PU/Rubber
Country Of Origin	:	--
Goods Exported To	:	--
Date Received/Date Test Started:		Mar 19, 2021
Date Final Information Confirmed:		Apr 01, 2021

Test Result Please Refer To Attached Page(S).

Should you have any query on this report, you may contact at gzfootwear@intertek.com

Authorized By:
For Intertek Testing Services Shenzhen Ltd.
Guangzhou Branch

Guiliang Dong
Senior Lab Manager

BF / lynnyang

Intertek Testing Services Shenzhen Ltd. Guangzhou Branch
深圳天祥质量技术服务有限公司广州分公司
Room 02, 1-8/F. & Room 01, E101/E201/E301/E401/E501/E601/E701/E801, No.7-2, Caipin Road, Guangzhou Science City, GETDD, Guangzhou, Guangdong, China
广州经济技术开发区科学城彩频路 7 号之二第 1—8 层 02 房、01 房 101、E201、E301、E401、E501、E601、E701、E801
Tel: +86 208213 9001 Fax: +86 20 82089909 Postcode: 510663
3/F., Hengyun Building, 235 Kaifa Ave., Guangzhou Economic & Technological Development District, Guangzhou, China
中国广州经济技开发区开发大道 235 号恒运大厦 3 楼
Tel: +86 20 83966868 Fax: +86 20 82228169 Postcode: 510730

TEST REPORT Number: GZHT91025679(S1)

Tests Conducted (As Requested By The Applicant)

Electric Hazard Resistant Footwear (EH) (ASTM F2412-18a, 9, Conditioned At 22℃ And 50% RH For 24 h And Testing Performed At The Same Conditions)

	Leakage Current	ASTM F2413-18 Requirement	Pass/Fail
Left:	0.2 mA	*	Pass
Right:	0.2 mA	*	Pass
Right:	0.2 mA	*	Pass

Remark: * = No Current Flow Or Leakage Current In Excess Of 1.0 mA Under The Application Of 18000 V At 60 Hz AC For 1 Minute.

Intertek Testing Services Shenzhen Ltd. Guangzhou Branch
深圳天祥质量技术服务有限公司广州分公司
Room 02, 1-8/F. & Room 01, E101/E201/E301/E401/E501/E601/E701/E801, No.7-2, Caipin Road, Guangzhou Science City, GETDD, Guangzhou, Guangdong, China
广州经济技术开发区科学城彩频路 7 号之二第 1—8 层 02 房、01 房 101、E201、E301、E401、E501、E601、E701、E801
Tel: +86 208213 9001 Fax: +86 20 82089909 Postcode: 510663
3/F., Hengyun Building, 235 Kaifa Ave., Guangzhou Economic & Technological Development District, Guangzhou, China
中国广州经济技开发区开发大道 235 号恒运大厦 3 楼
Tel: +86 20 83966868 Fax: +86 20 82228169 Postcode: 510730

TEST REPORT Number: GZHT91025679(S1)

Tests Conducted (As Requested By The Applicant)



End Of Report

This report is made solely on the basis of your instructions and/or information and materials supplied by you. It is not intended to be a recommendation for any particular course of action. Intertek does not accept a duty of care or any other responsibility to any person other than the Client in respect of this report and only accepts liability to the Client insofar as is expressly contained in the terms and conditions governing Intertek's provision of services to you. Intertek makes no warranties or representations either express or implied with respect to this report save as provided for in those terms and conditions. We have aimed to conduct the Review on a diligent and careful basis and we do not accept any liability to you for any loss arising out of or in connection with this report, in contract, tort, by statute or otherwise, except in the event of our gross negligence or wilful misconduct. No copy of the test report(except for full text copy) shall be made without the written approval by Intertek.

Intertek Testing Services Shenzhen Ltd. Guangzhou Branch
深圳天祥质量技术服务有限公司广州分公司
Room 02, 1-8/F. & Room 01, E101/E201/E301/E401/E501/E601/E701/E801, No.7-2, Caipin Road, Guangzhou Science City, GETDD, Guangzhou, Guangdong, China
广州经济技术开发区科学城彩频路 7 号之二第 1—8 层 02 房、01 房 101、E201、E301、E401、E501、E601、E701、E801
Tel: +86 208213 9001 Fax: +86 20 82089909 Postcode: 510663
3/F., Hengyun Building, 235 Kaifa Ave., Guangzhou Economic & Technological Development District, Guangzhou, China
中国广州经济技开发区开发大道 235 号恒运大厦 3 楼
Tel: +86 20 83966868 Fax: +86 20 82228169 Postcode: 510730

To : TRECK SA
Attention : Andres Gandara Date : Apr 01, 2021

Re : Report Revision Notification

Labtest Report Number GZHT91025679 date MAR 23, 2021

Please be informed that all the content recorded in the above captioned report will be void. This captioned report is now superseded by a revised Labtest Report, Number GZHT91025679(S1) , issued on Apr 01, 2021 .

Thank you for your attention

Authorized By:
For Intertek Testing Services Shenzhen Ltd.
Guangzhou Branch

Guiliang Dong
Senior Lab Manager

Intertek Testing Services Shenzhen Ltd. Guangzhou Branch
深圳天祥质量技术服务有限公司广州分公司
Room 02, 1-8/F. & Room 01, E101/E201/E301/E401/E501/E601/E701/E801, No.7-2, Caipin Road, Guangzhou Science City, GETDD, Guangzhou, Guangdong, China
广州经济技术开发区科学城彩频路 7 号之二第 1—8 层 02 房、01 房 101、E201、E301、E401、E501、E601、E701、E801
Tel: +86 208213 9001 Fax: +86 20 82089909 Postcode: 510663
3/F., Hengyun Building, 235 Kaifa Ave., Guangzhou Economic & Technological Development District, Guangzhou, China
中国广州经济技开发区开发大道 235 号恒运大厦 3 楼
Tel: +86 20 83966868 Fax: +86 20 82228169 Postcode: 510730